

By OnlineInterviewQuestions.com

Estimating and Costing MCQ Test

Take Estimating and Costing MCQ Test & Online Quiz to test your Knowledge

Below is the **Estimating and Costing MCQ** test that checks your basic knowledge of Estimating and Costing. This **Estimating and Costing MCQ Test** contains 20 Multiple Choice Questions. You have to select the right answer to the question. Finally, you can also take the Online Quiz from the Take **Estimating and Costing Quiz** Button.

Q1. The order of booking dimensions is

- A. Breadth, length, height
- **B. Length, breadth, height**
- C. Height, breadth, length
- D. None of the above

Q2. Pick up the item of work not included in the plinth area estimate

- A. Room area
- B. Wall thickness
- **C. Courtyard area**
- D. Verandah area

Q3. The item of the brick structure measured in sq.m is

- A. Brick edging
- **B. Broken glass coping**
- C. Reinforced brick work
- D. Brick work in arches

Q4. The plinth area of a building not includes

- A. Area of stair cover

- B. Lift and wall including landing
- **C. Area of cantilevered porch**
- D. Lift and wall including landing

Q5. The measurement is not made in square metres in case of

- A. Form works
- **B. R.C. Chhajja**
- C. Damp proof course
- D. Concrete Jeffries

Q6. How many bricks are there in 1 square meter?

- A. 40
- B. 45
- **C. 50**
- D. 55

Q7. Which is the most correct estimate?

- **A. Detailed estimate**
- B. Cube rate estimate
- C. Plinth area estimate
- D. Preliminary estimate

Q8. Which of the following estimate is a detailed estimate and is prepared to maintain the structure or work in proper order and safe condition?

- A. Revised estimate
- B. Item rate estimate
- **C. Maintenance estimate**
- D. Supplementary and revised estimate

Q9. Which of the following is the amount provided in the estimate and bill of quantities for some specialized work to be done by a specialized firm; whose details are not known at the time of preparing the estimate?

- A. Prime cost

- B. Capital cost
- **C. Provisional sum**
- D. Building cost index

Q10. What is required for preliminary studies of various aspects of a work or project?

- A. Revised Estimate
- **B. Abstract Estimate**
- C. Plinth Area Estimate
- D. Supplementary Estimate

Q11. The cube rate estimate is less accurate as compared to the plinth area estimate as the height of the building is also compared.

- **A. True**
- B. False

Q12. Which of the following is the most reliable estimate?

- **A. Detailed estimate**
- B. Cube rate estimate
- C. Plinth area estimate
- D. Preliminary estimate

Q13. What is the correct metric unit, while estimating the quantities for the construction of a building?

- A. Metre for length
- **B. Litre for capacity**
- C. Cubic metre for area
- D. Square metres for volume

Q14. brick walls are measured in sq. m if the thickness of the wall is

- A. 5 cm
- **B. 10 cm**
- C. 15 cm
- D. 20 cm

Q15. Which of the following statement is correct?

- A. In a gully trap, a water seal of 6 to 7.5 cm is provided
- B. The grating provided over gully traps is 23 cm square.
- **C. The gully trap collects waste water from the kitchen, sink, wash basins, etc.**
- D. The gully trap disconnects the sullage drain from the main drainage system

Q16. The rate of an item of work depends on

- A. Proportion of mortar
- B. Proportion of mortar
- C. Specifications of materials
- **D. All of the above**

Q17. The detention period in a septic tank is assumed

- A. 20 minutes
- B. 25 minutes
- **C. 30 minutes**
- D. 35 minutes

Q18. The minimum width of a septic tank is taken

- A. 85 cm
- B. 85 cm
- C. 65 cm
- **D. 75 cm**

Q19. Anti siphonage pipe is connected to

- A. Main soil pipe
- **B. Top of P trap W.C.**
- C. Bottom of P trap W.C.
- D. Side of water closet.

Q20. The 'centre line method' is specially adopted for estimating the

- A. Circular buildings
- B. Hexagonal buildings
- C. **Circular, hexagonal and other geometric shapes**
- D. None of the above

Please Visit OnlineInterviewquestions.com to download more pdfs